

CONTROL PANEL 1 PHASE- 60 HZ- 230 V

S. NO.	MATERIAL CODE	HP/KW	CAPACITOR		OVERLOAD RELAY	RESET	MCB	CUTOFFF RELAY	WEIGHT	DIMENSION (INCH)
			START	RUN						
1	9000001728	0.5/0.37	43-52 MFD,330 VAC	15 MFD, 440 VAC	6 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
2	9000001730	0.75/0.55	64-77 MFD,330 VAC	20 MFD,440 VAC	9 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
3	9000001731	1.0/0.75	88-106 MFD,330 VAC	20 MFD,440 VAC	10 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
4	9000001732	1.5/1.1	100-120 MFD,275 VAC	15 MFD,440 VAC	13 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
5	9000001733	2.0/1.5	189-227 MFD,230 VAC	20 MFD,440 VAC	16 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
6	9000001734	3.0/2.2	250-300 MFD,275 VAC	45 MFD,440 VAC	23 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
7	9000009829	5.0/3.7	189-227 MFD (2 NOS),220 VAC	80 MFD,440 VAC	32 AMP	MANUAL	*	35 AMP	7Lbs	8*10*6
8	9000018787	5.0/3.7	250-300 MFD,275 VAC	80 MFD,440 VAC	*	*	32 AMP	35 AMP		16*20*8.2
9	9000018682	7.5/5.5	250-300 MFD ,275 VAC (2 NOS)	45 MFD,440 VAC (2 NOS)	*	*	50 AMP	35 AMP		16*20*8.3
10	9000018681	10/5.5	250-300 MFD,275 VAC (2 NOS), 100-120 MFD,275 VAC (1 NOS)	50 MFD,440 VAC (2 NOS)	*	*	63 AMP	35 AMP		16*20*8.4
11	9000018423	15/11	250-300 MFD ,275 VAC (2 NOS), 189-227 MFD,230 VAC (1 NOS)	45 MFD,440 VAC (3 NOS)	*	*	100 AMP	35 AMP		16*20*8.5